This document summarises the requirements of the Victorian EPA Publication 788.1, Siting, Design, Operation and Rehabilitation of Landfills as published in October 2014 (Vic-BPEM) and discusses relevance for the Works Approval Application Supporting Document – Allawuna Landfill, Golder Associates, March 2015 (Allawuna WAA) and the Allawuna WAA's conformance (with justifications for deviations or alternatives).

SITA Australia Pty Ltd, as a result of this reconciliation, considers that the Allawuna Landfill WAA submitted satisfies the relevant requirements of the Vic-BPEM.

Siti	ng, Design, Operation an	d Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application Proposal	
	Section	Summary		
1	Introduction	Introduces the Vic-BPEM as EPA Victoria's Best Practice Environmental Management publication and is to be considered the source document for best- practice environmental management measures for landfills. The Vic-BPEM is intended to give direction on the best-practice siting, design, operation, performance and rehabilitation standards for landfills in Victoria.	The Vic-BPEM was used to guide development of the proposed Allawuna Lan preparation of the corresponding WAA, including supporting studies, as requir DER.	
1.1	Objectives of the Vic- BPEM	 The Vic-BPEM is a guideline aimed to provide existing and future operators of landfills, planning authorities and regulating bodies with information on potential impacts on the environment and how these are to be mitigated, a clear statement of environmental performance objectives, and information on how to avoid or minimise environmental impacts. In Victoria the Vic-BPEM is intended to be used as a default position for landfill siting, design, operation and rehabilitation. Landfill operators are required to meet the objectives and required outcomes by implementing the relevant best-practice measures, described as suggested measures, contained in the Vic-BPEM. The Vic-BPEM goes on to say that where a landfill operator believes that alternative means can achieve the objectives and required outcomes, a 	 The Vic-BEPM has been developed for use under Victorian regulations a conditions The Allawuna Landfill Works Approval Application (WAA) has been deve guidance provided by the DER during a scoping meeting in October 2014 The Vic-BPEM was adopted as the guidance document for technical dire used that were alternatives to the Vic-BEPM produced the required outcomethods familiar to the DER The DER's Technical Validation Checklist was used to ensure all environ were addressed. 	
		risk- based assessment can be proposed as an alternative measure.		
2	Waste Management Framework	Vic-BPEM summarises the statutory requirements for Victoria.	 The key guiding documents for the development of the Works Approval applic DER, PPMS_CL0593v1.0, Technical Validation Checklist The Western Australian Environmental Protection Act 1986 The Federal Environmental Protection and Biodiversity Conservation Act WA EPA, 2005, Separation Distances between Industrial and Sensitive L Department of Environment and Conservation, 2009, Landfill Waste Class Waste Definitions 1996 (As amended December 2009), and The Victorian EPA, 2014, Best Practice Environmental Management: Siti Operation and Rehabilitation of Landfills Guideline (Vic-BPEM). 	
3	Community Engagement	Vic-BPEM discusses the need for community engagement and provides community engagement models for consideration.	A comprehensive program of face to face meetings, public presentation, mail of advertisement, public display, newspaper editorials and a site tour were condu- development of this project. These activities were supported by willingness by answer any queries from the community, neighbouring premises or other inter- SITA is aware of opposition to the landfill and has endeavoured to address op refer Allawuna WAA Appendix L. SITA is also aware of a large portion of the community that is quietly supportive	
4	Classification of Landfills	 Vic-BPEM describes three types of landfills: Type 1 – Prescribed Industrial Wastes (not covered by Vic-BPEM. Type 2 – Putrescible Landfills (WA equivalent classification is Class II and Class III Landfills). Type 3 – Inert Landfills (WA equivalent classification is Class I Landfills). 	The Allawuna WAA proposes a Category 64 Class II putrescible landfill equiva Type 2 Landfill.	

1	Conclusions	
andfill design and uired by the WA		
and environmental		
14 rection. Methods comes and were		
onmental concerns		
lication have been:	Guidance documents used as recommended by the DER.	
ct 1999 (EPBC Act) Land Uses assification and		
Siting, Design,		
il outs, website ducted as part of the by SITA staff to erested parties.	Complies. Consultation undertaken complies with DoE, 2003, Interim Industry Guide to	
opponent's concerns,	Community Involvement.	
tive of the landfill.		
valent to Vic-BPEM	Complies.	
	Appropriate Category and Class nominated.	



1000	APPENDIX V
	Allawuna Landfill Works Approval Reconciliation with the EPA Victoria BPEM

Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification			Allawuna Farm Landfill Works Approval Application	
Section		Summary	Proposal	
5	Best Practice Siting Considerations	 The Vic-BPEM requires a preliminary investigation of all possible landfill sites to identify those sites with the best potential to be developed for landfilling. The investigation is to be conducted by the regional waste management group (RWMG) during development of the Regional Waste Management Plan (RWMP). To date and to our knowledge Western Australia has not developed a RWMP. Vic-BPEM mentions four landfill types. Listed in preferred order they are: Area method where an existing quarry hole is utilised Trench fill landfill where waste is placed above ground, and Valley landfill where natural topography assists to provide the void for landfill. 	 With the main guidance from the WA State Government being the directive of any new landfill developments off the Swan Coastal Plain SITA identified 26 potential sites with 19 of these sites shortlisted for assessment based on the Located off the Swan Coastal Plain Land for sale (freehold), or possibly for sale, subject to approaching the development of the analysis of the stances and manageable environmental risk profile Close to a main road for truck access Realistic travel distance from the Welshpool Transfer Station to the landfill Not in an area where landfill is explicitly prohibited. Upon further investigation of site specific features SITA selected Allawuna Far option. The Allawuna Farm site has been subjected to a thorough environment The investigation has shown no significant environmental impacts are likely to establishment or long term operation of the Allawuna Landfill. A copy of the confidential investigation matrix was provided in an email to the 2013. The confidential matrix can be resubmitted to the DER if necessary. SITA investigated 26 potential sites, including quarry voids, for a replacement Shale Road Landfill and settled on Allawuna Farm as the most appropriate loor. The chosen location on Allawuna Farm does not clearly fit into any of the four correspondence from the DER dated 3rd July 2012, which provided direction assessment, included as an attachment a map of watercourses in the area. T seasonally dry land depression (October to May) at the chosen location is desi as a minor watercourse. The landfill has been positioned predominantly on a side slope to the north of allow surface water from the relatively small upstream catchment to be diverted proposed landfill. The Allawuna WAA has been developed with thorough consideration of environmental relatively small upstream catchment to be diverted proposed landfill. 	
5.1.3	Groundwater	 Vic-BPEM requires new landfills to have an unsaturated zone of at least 2 m above the long-term undisturbed depth to groundwater unless: Additional design and management practices to protect groundwater quality are to be implemented, or Regional circumstances exist that warrant the development of a landfill to be sited otherwise. Where a 2 m unsaturated zone does not exist the base of the landfill should be raised to at least 2 m above the water table using a sub-base material with a cation exchange capacity (CEC) of about 10 mEq/100g. This CEC allows the sub-base to remove some contaminants from 	 The Allawuna Farm Landfill has been designed to provide a minimum unsatur below the bottom of waste. An additional 0.5 m buffer has been allowed for in landfill base. The clayey material on the site is not suitable for use as a clay liner material d high permeability and low CEC value. The clayey material can however be us with a geosynthetic clay liner (GCL) to form a system with similar performance compacted clay liner. This will be used with a geomembrane layer to form a c system that will have a similar performance to the liner system suggested by t The results of geotechnical investigations by Golder included as additional information the Allawuna WAA Appendix D). 	
		leachate seeping through the base of the liner, and further minimises the risk of groundwater pollution from the landfill.		

ı	Conclusions
of the DER to locate	Complies.
the following criteria:	Appropriate preliminary investigation undertaken.
e owner	
dfill, and	
arm as the best	
ental investigation.	
to arise from the	
e DER on 21 May	
nt landfill for the	Complies.
location.	Hydrology can be adequately
ur categories.	managed.
on for site The unnamed	
escribed on the map	
of the depression to rted around the	
ironmental factors	
urated zone of 2 m in the design of the	Complies.
l due to the relatively used in conjunction	
ce to a 1.0 m thick	
a composite liner	
y the Vic-BPEM.	
nformation (refer to	
Allawuna Farm and	Complies.



APPI	
Allaw	

Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification		Allawuna Farm Landfill Works Approval Application
Section	Summary	Proposal
Sites	use as a landfill rather than farming land and that the rehabilitation of an extractive industry site by landfill is not in itself sufficient justification for a landfill.	 identified insurmountable engineering challenges and unacceptable environmerendering the site unviable. SITA also investigated the potential of transporting waste by rail from Welshp afield from Allawuna Farm; however the costs to completely redevelop SITA's infrastructure for this mode of transport and developing rail siding infrastructure prohibitively high and not commercially viable.
.1.5 Buffer Distances	 The Vic-BPEM sites the following buffer distances from the landfill to sensitive land uses (receptors): 100 m from surface waters 500 m from building or structures 1500 m from an aerodrome for piston-engine propeller-driven aircraft, and 3000 m from an aerodrome for jet aircraft. 	 Refer to Best Practice Siting Considerations above for further discussion. The Allawuna WAA details the following attributes: 600 m from Landfill to Lot Boundary at the closest point 1900 m from Landfill to nearest neighbouring dwelling 4600 m from Landfill to Mount Observation Picnic Area 1000 m from Landfill to Wandoo National Park 270 m from leachate dams to 13 Mile Brook, and 350 m from Landfill to 13 Mile Brook. The landfill's stormwater retention and sedimentation structure, the stormwa 50 m from the landfill. The stormwater dam is considered part of the landfill infrastructure. There are no aerodromes in the area. The facility buildings are sited approximately 150 m from the landfill cells. T an issue as these facilities are associated with the landfill and hence not a sereceptor requiring a buffer under the Vic-BEPM.
.1.6 Geological Settir	 The Vic-BPEM requires a reasonable degree of assurance of the long-term protection of the landfill from an earthquake with landfills sited at least 100 m of a fault line. A further part of the assessment of the suitability of a potential site is the geotechnical stability of the ground on which the landfill will be placed 	 There is no record of any earthquakes within 4 km of the Site boundary, with t magnitude 2.5 earthquake 4 km to the north-east of the site. The area from the Darling Scarp to Merredin is an area of notable seismic act of the landfill is to the south-western edge of this zone of activity. A detailed geotechnical assessment has been conducted by Golder and has the part of the additional information (Allawuna WAA Appendix D).
.1.7 Flora and Fauna Protection	The Vic-BPEM states that landfills should not be sited on areas of critical habitats.	 A comprehensive Level 2 flora investigation of the affected works areas was a Australia. The key findings of the investigation were: The area is dominated by cleared cropland (87%) with low fauna habitat The remaining area (13%) is a seasonally dry minor watercourse, also w habitat value No declared weeds, threatened or priority flora were identified at the site The proposed development is likely to have minimal impact on the flora a survey area and surrounds. ENV completed a Level 1 fauna survey in the landfill development area. The fauna investigation were: Both habitat types present in the study area are of low fauna habitat value A comprehensive Black Cockatoo species specific assessment found minimal for the study area and surround minimal for the study area and surround minimal for the study area area of for the flora and surround minimal for the study area area of low fauna habitat value

ı	Conclusions
mental risks	
pool to sites further A's existing ure at each end were	
	Complies.
iter dam, is sited	
operational	
his is not considered ensitive land use	
n the nearest being a	Complies.
ctivity. The location	
s been included as	
s undertaken by ENV	Complies.
	Site investigations satisfy flora
at value	and fauna investigation
with low fauna	requirements.
te, and	
a and fauna of the	
e key findings of the	
llue minor ovidence of	
ninor evidence of	



APPENDIX V
Allawuna Landfill Works Approval Reconciliation with the EPA Victoria BPEM

Onting		and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application
	Section Summary		Proposal
			foraging under 10 of the 144 scattered Marri and Wandoo trees
			No evidence of roosting or breeding in any trees
			 Closest known Carnaby's Cockatoo roosting site is over 16 km away, and
			No evidence of Graceful Sun Moth habitat in the area.
			The Vegetation and Fauna Assessment Report has been included in the Allaw (Appendix K).
			Clearing in the development area has been determined as a 'not controlled ac Federal EPBC Act (refer to the Allawuna WAA Appendix U).
5.1.8	Infrastructure	Vic-BPEM requires consideration of the capacity of the road network to safely accommodate the increased traffic load, and with a minimum of disturbance to the local community by minimising the transport of waste	The development of the site will have a negligible effect on the road network in area and a minimal impact on Great Southern Highway vehicle volumes.
		through residential and other sensitive areas.	The landfill is located approximately 20 km to the west of York negating the ne trucks to go through or near York.
			The existing RAV Network 4 intersections along the haulage route are all suffice to accommodate the predicted 3% increase in local road traffic associated with development.
			Light vehicle movements for facility staff entering and departing the site from Y 2-3% increase in traffic between York and Allawuna at specific times in the more afternoon.
			A Traffic Impact Statement is included in the Allawuna WAA as Appendix J.
5.1.9	Surface Waters	Vic-BPEM states that putrescible waste landfills must be located more than 100 m from surface waters. Landfills should not be located in a floodplain. Where landfills are within a floodplain, additional engineering	The landfill is sited no less than 350 m from Thirteen Mile Brook. The Thirteen plain does not extend to the landfill.
		and management controls must be in place to ensure that the facility will be protected from flooding, erosion by floodwaters and infiltration from perched water table.	There is a stormwater dam proposed to be constructed within 100 m of the lar stormwater dam is part of the landfill infrastructure and will act as a water stora retardation structure. It will have a storage capacity of approximately 36 000 m
			A small retention pond (temporary stormwater storage dam) is also part of the infrastructure. The retention pond will collect shallow ground water from the la
			A self-draining sediment management structure is proposed downstream of the to manage sediment from the landfill site.
			Diversion bunds will be constructed as part of the stormwater management sy landfill to divert the majority of the catchment around the landfill site directly to dam.
			The surface water management systems proposed will ensure that the landfill contaminating surface water. For further detail refer to the Surface Water, Gro Leachate Management Plan (Allawuna WAA Appendix E).
5.1.10	Land Ownership	Vic-BPEM describes requirements for landfills on Crown land.	The current owner of Allawuna Farm, Robert Henry Chester, and SITA has a I Understanding in place providing a binding agreement to transfer ownership o subject to certain conditions.

Ś

1	Conclusions
and	
awuna Landfill WAA	
action' under the	
in the metropolitan	Complies.
need for haulage	Traffic impact assessed as minimal.
fficiently developed vith the landfill	
n York represents a morning and	
en Mile Brook flood	Complies.
andfill. The orage and) m ³ .	Landfill not located within 100 m of natural surface waters.
ne landfill landfill footprint.	
the stormwater dam	
system above the to the stormwater	
fill presents no risk of Groundwater and	
a Memorandum of of the property	Not applicable





Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification			Allawuna Farm Landfill Works Approval Application	
Section		Summary	Proposal	
6	Best Practice Design	The Vic-BPEM states that the design of a landfill facility will be influenced by the existing natural environment, adjacent land uses, available infrastructure, waste to be received and the need to provide integrated waste management facilities for both disposal and recycling options.	SITA will be the owner of Allawuna Farm prior to construction work commence Addressed in the following sections.	
6.1	Environmental Assessment	 Vic BPEM states that environmental assessment should contain: Meteorological data Hydrogeological assessment Water management information including: Water balance for the site and estimated volume of leachate to be generated Leachate collection, storage facilities, treatment and disposal Stormwater diversion banks and/or cut-off drains and storage dams Fire-fighting equipment and water supply Wheel washes Landfill gas and odour control, and Noise assessment. 	 The Allawuna WAA has included the following environmental assessments: Rainfall, temperature and solar radiation data was established from the Meteorology (BOM) thirty year climate normal dataset for the years 1967 Post Office weather station (meteorological data was determined and us the HELP model to predict leachate generation) (refer to WAA Appendix Hydrogeological assessment, a network of bores were developed over t and surrounding area to determine the local geology, water table and gr pattern (refer to WAA Appendix E) Water management information including: Water balance for the site and estimated volume of leachate to be g Leachate collection, storage facilities, treatment and disposal Stormwater diversion banks and/or cut-off drains and storage dams Fire-fighting equipment and water supply (refer to WAA Appendix R) Wheel wash Landfill gas (refer to WAA Appendix G) Odour assessment (refer to WAA Appendix I) and Noise assessment (refer to WAA Appendix I). 	
6.2	Site Layout	 The Vic-BPEM states that the landfill and associated facilities should be designed to minimise potential environmental impacts, health and safety risks, encourage recycling and make the most efficient use of resources on site. A series of cells each taking less than two years to fill, after which they are immediately rehabilitated. A weighbridge is required at landfill sites in Municipalities listed in Schedule C of the Victorian EP Act. 	 The Allawuna Farm Landfill will serve as a final disposal site for waste deliver Welshpool Waste Transfer Station and the Lansdale Waste Transfer Station. extensive investment in resource recovery in the Perth region resulting in pre unrecyclable materials being delivered to its waste transfer stations. Prior to trucks for transport to landfill SITA sorts waste at the waste transfer stations to recyclable material contained in the waste. The Allawuna Farm Landfill will be developed in a series of cells. The Allawut the first two cells of the development. Each cell is designed to accommodate prior to the next cell being built. Cell 1 will have a total fillable airspace of approximately 781 000 m³ which ref 4 years operational capacity however it will be comprised of sub-cells 1a (app and 1b (approx. 348 000 m³), each of which are expected to operate for a ma before being capped and rehabilitated. The fillable capacity of Cell 2 will be a 968 000 m³ however this will also be comprised of sub-cells (2a and 2b) that and operated in a manner that minimises as much as possible the duration of capping and rehabilitation. The Allawuna landfill facility will include a weighbridge to weigh incoming and movements. 	
6.3	Liner and Leachate Collection System	The Vic-BPEM requires landfill liners to comprise of up to five components: Sub-base 	The material properties of the liners have been nominated in the Technical S construction of cells 1 and 2 (WAA Appendix M) and have been specified to r requirements of the Vic-BPEM.	

1	Conclusions
icing.	
- 5	Complies.
	Technical aspects of landfill design comply with the requirements of the Vic-BPEM.
e Bureau of 61-1990 for the York used as input data in ix E) the landfill footprint groundwater flow	Complies.
generated	
s R)	
ered to the a. SITA has an edominantly b being loaded on to recover	Complies.
runa WAA relates to e 3-4 years of waste	
epresents 3 to oprox. 433 000 m ³) aximum of 2 years approximately t will be constructed of cell use before	
d outgoing transport	
Specification for the meet the	Complies.



•		nd Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	
	Section	Summary Clay or geosynthetic clay layer Geomembrane and protection layer Drainage layer/leachate collection system, and Geotextile. In designing a landfill liner, the landfill designer must ensure that the liner system is geotechnically stable between components and as a total system.	Allawuna Farm Landfill Works Approval Application Proposal The proposed liner configuration is listed below: Compacted and rolled subgrade A GCL installed over the subgrade and side slopes A GCL installed over the subgrade and side slopes A 2.0 mm thick double textured HDPE geomembrane liner will be placed GCL A non-woven geotextile cushion layer will be placed on top of the HDPE protective layer A 300 mm aggregate layer will be laid on top of the cushion layer to act a drainage layer Leachate collection pipes will be installed in the drainage layer, and
			 A separation geotextile layer will be placed on top of the aggregate to selayer from the waste. Stability modelling for the complete landform has previously been undertaken IV EPA Referral process. For the Allawuna WAA stability modelling was under the embankment design and interim waste batters during the construction and 1A and 1B and Cell 2. Both circular slope and sliding block (shear) failure more considered. Pseudo static modelling was also undertaken to test the stability under lateral seismic loading, as would be experienced during an earthquake.
6.3.1	Sub-Base	The Vic-BPEM states that all plans for the construction of a sub-base must be verified and approved by a geotechnical engineer. Construction of the sub-base must be included in the construction quality assurance (CQA) plan.	 Geotechnical information is provided by Golder as part of the additional inform WAA Appendix D). Golder concludes that the lateritic materials present at the compact well and are suitable for civil construction works. A Technical Specification has been included in the Allawuna WAA Appendix N requirements for construction quality assurance are detailed in the CQA Plan WAA Appendix M) The requirements for the landfill sub-base are defined in the
6.3.2	Clay Liner	The Vic-BPEM requires the clay component to be at least 1 m thick and have a hydraulic conductivity of less than10 ⁻⁹ m/s.	The Allawuna WAA proposes the use of GCL in conjunction with 500 mm thic compacted clayey site material.
6.3.3	Geosynthetic Clay Liner (GCL)	The Vic-BPEM states the GCL can be used as an element of composite base and side liners. The suitability of GCL lining for bottom, side slope and capping of landfills requires an assessment of water and gas flow, contaminant transport and stability.	The GCL will be installed over the base of the landfill cells and on the side slo shall have properties as nominated in the Technical Specification in accordan BPEM requirements. Installation of GCL will be observed and verified by an appropriately qualified Assurance Inspector, QAI) independent of the construction contractor and line The GCL will be covered by a layer of HDPE which is intended to act as the a
6.3.4	Geomembranes	 The Vic-BPEM states that the key properties required for geomembranes are thickness, strength, the ability to resist or accept stress and deformation, tensile strength, puncture resistance, slope stability-interface friction, long term mechanical performance, durability and resistance for degradation. Geomembranes are to be used only as a barrier and not to serve any load-bearing or structural function. Landfill design should minimise stress on the geomembrane. 	 landfill gas migration. A 2 mm thick HDPE geomembrane liner will have properties as in the Technic accordance with the Vic-BPEM requirements. The HDPE will be placed direct which will also limit contaminant migration and control landfill gas migration. The key properties of the HDPE are detailed in the Technical Specification (A WAA Appendix M). Installation of the HDPE liner will be observed and verified by an appropriately party independent of the construction contractor and liner contractor. Two dimensional modelling was undertaken using the SLOPE/W modelling part the stability of the landfill at the following stages of development:

ı	Conclusions
ed directly above the	
E liner to serve as a	
t as a leachate	
serve as a separation	
en as part of the Part dertaken to validate nd filling of sub-Cells nodes were ty of the structures e.	
rmation (refer to he landfill site	Complies.
< M and the n (Allawuna Landfill these documents.	
ick layer of	Not applicable.
lopes. The GCL ance with the Vic-	Complies.
d third party (Quality ner contractor.	
attenuation layer for	
nical Specification in ectly above the GCL	Complies.
Allawuna Landfill	
ely qualified third	
package to assess	



ວແທ		d Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application
	Section	Summary	 Sub-Cell 1A filled with waste Cell 1 complete and partially capped, and Cell 2 complete and partially capped. For each stage, safety factors associated with circular slope and sliding block evaluated. Typical values for material properties of each material were used in the model stress on both the GCL and the HDPE liners the plane of weakness was design the upper surface of the HDPE and the protective non-woven geosynthetic current For further detail refer to the Stability Analysis and Liner System Integrity Association (Allawuna WAA Appendix D).
6.5.3	Leachate Collection System	 The Vic-BPEM states that the maximum leachate head on the liner is 0.3 m. The liner is to be sloped into the leachate collection pipes which in turn are sloped to the leachate collection sump. These slopes should be a minimum 3% to the pipes and 1% to the sump. The drainage layer is to be at least 300 mm in depth and with a hydraulic conductivity of greater than 1x1 x10⁻³ m/s. Properties of aggregate used in the drainage layer are: Aggregate size to be less than 50 mm and greater than 20 mm Fines content to be less than 1%, and Should not contain calcareous material that would be subject to chemical attack. The recommended maximum pipe spacing is 25 m. Giroud's equation to be used to design the liner slope and pipe spacing to ensure the maximum design leachate head is not exceeded. Manning's equation is used to derive the required pipe size based on leachate flow rate is derived using a model such as the Hydrological Evaluation of Landfill Performance (HELP) model. The volume of leachate generated should be based on a 1-in-20 year storm event after one lift of waste has been placed in the landfill. 	 Operational management practices will be adopted to ensure the maximum he over the liner is less than 0.3 m. The Vic-BPEM landfill liner slope requirements are determined based on an ic shape with ridges on the cell floor between collection valleys, enabling the use equation. The proposed Allawuna Landfill cell design takes advantage of the site to create a uni-directional fall towards the landfill sump without intermedia Giroud's equation is not applicable under such a scenario. The fall of the bas generally 3% towards the landfill sump, with a minimum of 2.5%. This is consprovide appropriate drainage and prevent ponding on the liner. Using Manning's equation and the leachate generation output from the HELP appropriate leachate pipe sizing was determined. The thickness requirements and the buckling pressure of the leachate pipes h determined using the American Society of Mechanical Engineers ASME Boile Vessel Code Case N-755. The leachate system has been appropriately stress tested for typical, 1-in-10 record rainfall cycles. To ensure a 'worst case scenario' in the model the waste mass is initialised at capacity to retain incoming rainwater. A 300 mm aggregate layer will be laid on top of the cushion layer to act as a layer. The hydraulic conductivity of the drainage layer will be greater than 1 x The Technical Specification (Allawuna Landfill WAA Appendix M) stipulates tha aggregate properties to be used.
6.4	Construction Quality Assurance	Vic-BPEM requires the development and implementation of a construction quality assurance (CQA) plan.	(Allawuna Landfill WAA Appendix E) for more detail. A Construction Quality Assurance (CQA) Plan, included in the Allawuna Land Appendix M, will be used by the QAI and Superintendent when overseeing the

ı	Conclusions
k failure were	
lelling. To minimise signed to be between cushion layer.	
sessment Report	
head of leachate	Complies.
idealised landfill se of Giroud's e natural slope of the liary ridge lines. ase of the cells is nsidered sufficient to	
P model, an	
have been iler and Pressure	
0 and highest on	
at saturation, with no	
e) years of rainfall vas evaluated by	
l leachate drainage x10 ⁻³ m/s. the required	
te Management Plan	
ndfill WAA in he construction	Complies.



Sitin		Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application
	Section	Summary	Proposal
		 The CQA plan must be able to verify that: Materials used comply with specifications, and Method of construction/installation is appropriate and design requirements have been met. The CQA plan must contain the material/construction specifications, testing methods, testing frequency, corrective action and provide for appropriate documentation procedures. CQA documentation will be verified by an environmental auditor and the plan will be used by the environmental auditor as part of auditing cell 	works. The QAI of the project will be responsible for CQA of the earthworks a installation. A Construction Plan for liner installation will be prepared by the li accordance with the Technical Specification (Allawuna Landfill WAA Appendi by the Superintendent. The lining contractor will conduct all destructive and r testing which will be witnessed by the Superintendent. The Superintendent w report at the completion of the construction to confirm that the required construction met.
		construction.	
5.1	Stormwater Management	Storage ponds and other drainage measures should be designed to contain and control rainfall run-off for a 1-in-20-year storm event.	A stormwater dam embankment will be constructed of low permeability clay n positioned south and downstream of the landfill.
		Storm events up to 1-in-100-year recurrence intervals should also be considered.	The stormwater dam will collect surface runoff from around (outside) the land sediment control structure.
			The sizing of the stormwater dam has been based on construction water need stormwater retention characteristics as the dam is sited below the landfill.
			An appropriately sized overflow weir has been designed for the stormwater dare tention and controlled release of water into the minor watercourse leading to Brook.
			The surface water drainage systems have been designed to prevent the interstormwater and leachate.
			Appropriately sized culverts and drains will be used to control stormwater from embankments, hardstands, buildings and hill slopes at the site.
			Refer to the Allawuna Landfill Surface Water, Groundwater and Leachate Ma (Allawuna Landfill WAA Appendix E) for more detail.
.5.2	Leachate Management	The Vic-BPEM states that a water balance should be modelled over at least two consecutive wet years (90th percentile) and any ponds containing leachate should have a freeboard of at least 0.5 m.	The leachate dam was modelled for 2 consecutive wet (90th percentile) years generated leachate. The leachate dam will be managed to ensure a minimum mm is maintained at all times.
5.3	Groundwater Management	The Vic-BPEM requires consideration of groundwater in situations where sites extract groundwater, landfills below the water table.	There are no plans to extract groundwater from beneath the site for use on th
	Managoment		The groundwater on the site will be protected from landfill leachate by a layer geomembrane, a layer of GCL overlain on natural low permeability clayey so
			The landfill liner will be a minimum of 2 m above the drainage constrained group below the landfill.
			Further discussion on the groundwater beneath the landfill is included in the H Site Characterisation Report (Allawuna Landfill WAA Appendix E).
.6	Groundwater	Vic-BPEM states that a landfill must not impact on beneficial uses of groundwater, the design of the landfill must consider the local hydrogeological environment. Issues to be considered include:	There will be no less than a 2 m thick unsaturated zone below the landfill line be no uplift forces on the liner.

1-1-

ı	Conclusions
and liner lining contractor in dix M) and approved non-destructive will prepare a CQA struction quality is	
material and	Complies.
dfill and double as a	
eds and not	
dam to allow to the Thirteen Mile	
eraction of	
om the roads,	
anagement Plan	
rs of rainfall um freeboard of 500	Complies.
the farm.	Complies.
er of HDPE oils.	
roundwater level	
Hydrogeological	
er; hence there will	Complies



Siting		d Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application
	Section	Summary	Proposal
		Liner upliftGroundwater monitoring bores, and	A series of nineteen monitoring bores have been installed. The complete received sampling events is included in the additional information.
		 Groundwater recovery bores. 	Generally groundwater is not used on Allawuna Farm as it is too saline. Curr proposed future use for groundwater on Allawuna Farm.
6.7	Air Quality	The Vic-BPEM states that landfills can pose a risk to air quality through landfill gas, odour and dust.	Addressed in the following sections.
6.7.1	Landfill Gas	The Vic-BPEM states that the most appropriate way to evaluate the level of risk posed by landfill gas from an individual site is to conduct a site- specific landfill gas risk assessment.	The landfill gas quantities have been estimated using the GasSim V2.5 (GasS landfill gas generation modelling was carried out by Golder Associates as det Allawuna Landfill Gas Assessment Report (Allawuna Landfill WAA Appendix
			During landfill operation landfill gas will be collected and flared to convert the less harmful carbon dioxide. When a sufficient quantity and quality of landfill produced the gas may be used as fuel for electricity generation. A Landfill Ga Plan has been prepared specifically for Allawuna Farm Landfill and describes network, monitoring and includes landfill gas generation predictions (refer to t Landfill WAA Appendix G).
6.7.2	Air Toxics	The Vic-BPEM recommends that assessment of air toxics should be undertaken as part of the landfill gas risk assessment (LFGRA). Also, if necessary, a monitoring plan consistent with world best practice to	It is generally accepted that air toxins are present in landfill gas emitted from a landfills. The type and quantity of toxins is a function of the landfill construction system and capping system), the type of waste disposed of within the landfill, waste and the efficiency of landfill gas extraction and destruction. The conser-
		ensure protection of public health should be developed and implemented for air toxics. Air toxics monitoring should include ambient air at the boundary of the site.	emitted toxins is a function of the quantity of toxins emitted and the proximity source of emission. With the proposed landfill being fully lined, having an act extraction system, receiving only Class II waste and at relatively low annual to the fact that the nearest neighbouring residential property is in excess of 10 ti required buffer distance from the landfill facility (1.8 km vs 150 m), air toxins a be a health concern.
6.7.3	Odour	The Vic-BPEM states that, at all times, a landfill must be managed to prevent offensive odours beyond the boundary of the premises.	Detailed odour modelling for the proposed landfill was undertaken by Environ Pty Ltd. The complete report is attached to the Allawuna WAA as Appendix C
			The modelling indicates that for the proposed operational times, procedures a all odour generated would be maintained well within the Farm boundary.
6.7.4	Dust Emissions	The Vic-BPEM discusses mitigating measures to minimise dust and suggests that in certain circumstances dust monitoring may be required.	The Allawuna WAA discusses mitigation measures for dust both during constru- operation of the landfill (refer to the Allawuna Landfill WAA Appendix N for the Risk Assessment).
6.8	Bioreactor Landfills	The Vic-BPEM states that waste degradation in a conventional 'dry tomb' landfill is inhibited by the lack of moisture within the waste and outlines the benefits of leachate recirculation and/or fresh water infiltration in a 'bioreactor landfill' to promote the conditions necessary for micro- organisms to achieve rapid rates of waste decomposition.	Most landfills incorporate some degree of leachate recirculation and/or fresh we however, are not classified as bioreactor landfills and hence are also not "dry Leachate recirculation is widely used in WA to manage leachate volumes and to increase the rate of waste decomposition and landfill stabilisation.
			There will be a degree of fresh water infiltration and leachate recirculation with but not to the extent that the landfill will be classified as a bioreactor landfill.
6.9	Noise	Vic-BPEM states that site operations should be set out to minimise noise impacts by using natural and/or constructed features such as earthen bunds and depressions as well as minimising steep-haul roads and alternative types of reversing beepers could be adopted.	A comprehensive noise assessment found that predicted noise levels at the n were within the guideline limits for times of day during both the construction at phases of the landfill (refer to the Allawuna Landfill WAA Appendix I).
6.10	Traffic Considerations	The Vic-BPEM suggests limiting speed of trucks, site layout, traffic islands, recessed entrance and wheel wash facilities will minimise impact on local community.	A detailed traffic assessment was undertaken by Shawmac Traffic Engineers Allawuna Landfill WAA Appendix J). The intersection of the site access road Southern Highway will be upgraded to meet the requirements of Main Roads signage will be installed along Great Southern Highway identifying the landfill

1-1-

n	Conclusions
ecord of groundwater	
rrently there is no	
	Complies.
sSim) model. The etailed in the x G).	Complies.
e methane into the Il gas is being Gas Management es the gas collection o the Allawuna	
n most putrescible tion (base lining II, the quantity of sequence of the y of a receptor to the ctive landfill gas tonnages as well as times the EPA are not deemed to	Not applicable.
onmental Alliances G.	Complies.
and waste volumes,	
struction and he Environmental	Complies.
n water infiltration ry tomb" landfills. nd wet the dry waste	Not applicable.
ithin the waste mass	
nearest residence and operational	Complies.
s (refer to the d and Great s WA. Appropriate ill and warning of	Complies



	nd Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application
Section	Summary	Proposal
		 trucks entering and departing the site. An access road across Allawuna Farm, from the intersection with the highway will be constructed as part of the works. The road will be aligned to minimise cropping, minimise the removal of remnant vegetation, maintain a safe geome movements. The road pavement will be sealed to an appropriate standard fo vehicle movements. The access road will be fenced to keep livestock and oth road. A dual lane creek crossing will also be installed on the property across Brook to enable all weather vehicle access to the landfill. The general configuration of the office and other infrastructure areas is indicated. A truck wheel cleaner/mud shaker will be constructed adjacent to the leachated hardstand area will be established for the storage of equipment.
Site Security and Fencing	The Vic-BPEM recommends fencing requirements as a wire mesh fence at least 2 m high constructed around the landfill site perimeter.	A 1.8 m high security fence topped with barbed wire will be erected around th landfill operations area to prevent unauthorised site access, capture windblow access by livestock and native fauna.
Low-Risk Rural Landfills	 The Vic-BPEM states that small rural municipal Type 2 landfills may use Type 3 landfill design criteria for capping and lining systems in the following circumstances: It meets or exceeds the Vic-BPEM buffer requirements It receives less than 20 000 tonnes of waste per annum Wastes are at least two metres above the long-term undisturbed groundwater level It is not located in Segment A groundwater, and Financial assurance to the satisfaction of EPA is in place. All the above criteria must be met for a landfill to be considered a low-risk rural landfill. 	This is a specific class of landfills in Victoria. It is not relevant to WA or the si
Best Practice Operation	The Vic-BPEM requires protection of the environment from landfilling activities in addition to the landfill design and construction. Elements of a landfill's operations that need to be considered are: Environmental management Financial assurance Waste minimisation Waste acceptance Waste pre-treatment Waste placement Utter control Dust and air emission control Fires Contingency planning Management of chemicals and fuel	Landfill operations are described in the Allawuna Landfill WAA with reference Acceptance Manual (Appendix Q) and Emergency Procedures Guide and Co (Appendix Q). Additional information relating to emission management can be found in the S Groundwater and Leachate Management Plan (Allawuna Landfill WAA Apper Landfill Gas Management Plan (Allawuna Landfill WAA Appendix G).
	Section Section Site Security and Fencing Low-Risk Rural Landfills Best Practice	Section Summary Site Security and Fencing The Vic-BPEM recommends fencing requirements as a wire mesh fence at least 2 m high constructed around the landfill site perimeter. Low-Risk Rural Landfills The Vic-BPEM states that small rural municipal Type 2 landfills may use Type 3 landfill design criteria for capping and lining systems in the following circumstances: It meets or exceeds the Vic-BPEM buffer requirements It receives less than 20 000 tonnes of waste per annum Wastes are at least two metres above the long-term undisturbed groundwater level It is not located in Segment A groundwater, and Financial assurance to the satisfaction of EPA is in place. All the above criteria must be met for a landfill to be considered a low-risk rural landfill. Best Practice Operation The Vic-BPEM requires protection of the environment from landfilling activities in addition to the landfill design and construction. Elements of a landfill's operations that need to be considered are: Environmental management Financial assurance Waste minimisation Waste pre-treatment Waste pre-treatment Waste placement Waste cover Litter control Dust and air emission control Fires Contingency planning

ı	Conclusions
ay to the landfill area, e disruption to netry for truck for regular heavy ther fauna off the s the Thirteen Mile rated in the WAA.	
he perimeter of the own litter and prevent	Complies.
site.	Not applicable.
e to the Waste ontingency Plan Surface Water, endix E) and the	Complies.



Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification			Allawuna Farm Landfill Works Approval Application
	Section	Summary	Proposal
		 Noxious weed control, and 	
		Performance monitoring and reporting.	
7.1	Environmental Management	The Vic-BPEM requires in accordance with the Waste Management Policy (<i>Siting, Design and Management of Landfills</i>), which is a Victorian document; the holder of a licence for a landfill site is required to develop an environment improvement plan.	SITA is certified for the management of the Environment (ISO 14001), Health 4801) and Quality (ISO 9001). SITA is accredited to ISO Standard 14001:200 transfer station environmental management system. SITA intends to use its v experience in the effective operation of landfill facilities via its accredited system facility.
			Environmental improvement measures will be incorporated into the facility's o
7.2	Financial Assurance	The Vic-BPEM requires financial assurance for all licensed landfills.	It is not the practice in Western Australia that all landfills have financial assura
7.3	Waste Minimisation	The Vic-BPEM states that landfilling is the least preferred option in the waste hierarchy. Every practicable opportunity should have already been	SITA was the recipient of the Australian Business 2013 Environmental Sustain
		taken to avoid waste production and remove recyclable material from the waste stream before it arrives at the landfill.	In 2013 SITA diverted 130 000 tonnes of waste from landfill in Perth.
			The Allawuna Farm Landfill will serve as a final disposal site for residual wast previously been sorted at SITA's waste transfer station to recover recyclable received at SITA's waste transfer station to recover received at SITA's waste transfer station to recover received at SITA's waste transfer station to recover received at SITA's waste transfer station to received at SITA's waste transf
7.4	Waste Acceptance	The Vic-BPEM requires resources and infrastructure to adequately manage the arrival and receipt of waste.	A 30 m long weighbridge certified to 100 tonnes will be installed for the weigh material.
			Signs will be established, random verification inspections, video cameras will installed and procedures will be implemented to deal with such wastes.
			Details of staff responsibilities and waste acceptance criteria are included in the Landfill Waste Acceptance Manual (refer to the WAA Appendix Q).
7.5	Waste Pre-treatment	The Vic-BPEM requires pre-treatment of waste prior to landfilling is intended to reduce the long-term risk posed by the waste and to improve general landfill performance.	The Allawuna Farm Landfill will serve as a final disposal site for residual wast previously been sorted at SITA's waste transfer station to recover recyclable r
7.6	Waste Placement	The Vic-BPEM requires that the thickness of the waste layer should not exceed 0.5 m and the compactor should make 3-5 passes over the waste to maximise compaction.	This is SITA's standard operating practice on all its landfills.
_		The tipping face should be kept to less than 30 m in length. The total height of the layers combined in the lift should be less than 2 m.	
7.7	Waste Cover	The Vic-BPEM states that an essential part of landfilling operations is the placement of cover over wastes.	SITA will use soil as the daily cover material. All waste will be covered to a th
7.8	Litter Control	The Vic-BPEM requires a litter control strategy.	Litter control measures are proposed in detail in the WAA (refer to the Environ Assessment in Appendix N).
7.9	Fires	The Vic-BPEM requires a fire control strategy.	Fire management procedures for the facility are included in the Emergency Pl and Contingency Plan (Allawuna Landfill WAA Appendix Q).
			A site specific Fire Management Plan has also been developed in consultation copy of the Fire Management Plan has been included in the WAA as Appendi
7.10	Contingency Planning	The Vic-BPEM requires contingency plans to be developed.	Contingency measures are discussed in the Emergency Procedures Guide ar Plan (Allawuna Landfill WAA Appendix Q).
7.11	Management of Chemicals and Fuels	The Vic-BPEM requires storage and handling of flammable and combustible liquids should be in accordance with the provisions of AS 1940–2004 <i>The storage and handling of flammable and combustible liquids and Bunding guidelines</i> (EPA publication 347).	Fuel stored on site will be kept in an approved bunded tank, in line with the Da Safety (Storage and Handling of Non-explosives) Regulations 2007 and Austr 1940 The storage and handling of flammable and combustible liquids.

ı	Conclusions
h and Safety (AS 004 for its landfill and wealth of stems to operate the	Complies.
operational plans.	
rance.	Not applicable.
ainability Award.	Complies.
ste that has e materials.	
hing of incoming	Complies.
ll be strategically	
the Allawuna	
ste that has e materials.	Complies.
	Complies.
thickness of 300 mm.	Complies.
ironmental Risk	Complies.
Procedures Guide on with DFES. A	Complies.
dix R). and Contingency	Complies.
Dangerous Goods stralian Standard AS	Complies



Sitin	Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification		Allawuna Farm Landfill Works Approval Application	
	Section	Summary	Proposal	
7.12	Disease and Vector Control	The Vic-BPEM requires the control of birds and other vermin at the facility.	Disease vectors and vermin control is discussed in the WAA (refer to the Enviro Assessment in Appendix N).	
7.13	Noxious Weed Control	The Vic-BPEM requires measures to control weeds.	As part of managing the Allawuna Farm Landfill, SITA has undertaken to improve Thirteen Mile Brook. Weed management strategies will be developed and imple site.	
			Keeping the area dieback free will also be an important aspect of the operations and the wheel wash for departing trucks will reduce the risk of vehicles transport	
7.14	Monitoring and Reporting	The Vic-BPEM requires performance monitoring and annual reporting.	A biannual monitoring program for the bores installed on the Allawuna landfill si effect. Seven bores were installed in winter 2012 and an additional six bores w autumn 2013. This has been followed more recently by the installation of a furt December 2014.	
			Monitoring and reporting requirements imposed on the facility by the operating adhered to. Monitoring will include groundwater, surface water, dust, noise, lan leachate.	
8	Best Practice Rehabilitation and Aftercare	The Vic-BPEM requires rehabilitation and aftercare to be considered very early in the landfill design and operation phase.	Addressed in the following sections.	
8.1.1	Rehabilitation Plan	The Vic-BPEM requires a conceptual rehabilitation plan to be developed as part of the initial landfill design. The rehabilitation plan should include:	The Allawuna WAA includes a conceptual rehabilitation plan for the proposed la	
		The potential after uses of the site, taking into consideration current and likely future land use in the area surrounding the site		
		 Operational requirements, to ensure that the capping is designed to suit the intended after use 		
		 Surface contours before and after settlement 		
		 Specifications and materials to be used in the final cap, and 		
		 Preservation/installation of environment performance control or monitoring features. 		
8.1.2	Progressive	Landfill cell rehabilitation works include:	The landfill will be capped progressively throughout its operational life (the land	
	Rehabilitation	 Capping and revegetation in accordance with regulatory requirements 	facilitates this activity) and the leachate and landfill gas management systems we and amended or replaced when necessary (refer to the WAA Appendix E and A	
		 Installation and ongoing maintenance and replacement of gas and leachate collection infrastructure, and 		
		 Decommissioning of infrastructure no longer required. 		
8.1.3	Triggers for Rehabilitation	The Vic-BPEM makes the following recommendations for initiating rehabilitation of a landfill cell:	The Allawuna WAA includes a conceptual rehabilitation plan for the proposed la	
		The landfill cell contents have reached the approved pre-settlement contours, allowing sufficient height to build the landfill capping within the pre-settlement contours	Progressive closure and rehabilitation consistent with these requirements will be	
		• Further filling of the cell is operationally no longer required or feasible		
		There has been a lawful direction to cease filling the cell		
		The landfill is to be closed, or		
		Two years have elapsed since commencement of filling.		
		A landfill licence-holder should, where operationally practicable, sequence operations to complete the filling of each cell in turn, rather than leaving		

1	Conclusions
vironmental Risk	Complies.
prove the quality of nplemented at the	Complies.
ions at the facility porting the fungus.	
Il site is currently in s were installed in further six bores in	Complies.
ng licence will be landfill gas and	
	Complies.
d landfill.	Complies.
andfill cap design ns will be maintained nd Appendix G).	Complies.
d landfill.	Complies.
II be carried out.	





Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification		Rehabilitation of Landfills (EPA Victoria, October 2014) Specification	Allawuna Farm Landfill Works Approval Application	
	Section	Summary	Proposal	
		one or more partly filled cells inactive and not fully rehabilitated. Where cells cannot be fully rehabilitated due to the layout of the site and the sequencing of filling, intermediate (temporary) capping must be installed.		
8.1.4	Site After Use	The Vic-BPEM requires proposals for the use of the filled landfill site to be flexible enough to allow for changes in community attitudes or planning requirements in the long period between commencement of landfilling and final rehabilitation. This may necessitate regular reviews of after use options as a way of ensuring that the operation of the landfill does not alienate desired after uses of the site.	Due to the rural setting of the landfill, it is most unlikely that there will be any c community attitudes or planning requirements that would change the ultimate	
8.1.5	Settlement and Final Surface Profile	The Vic-BPEM states that the gradient of a completed cap should be sufficient to prevent water ponding on the cap to minimise infiltration through the cap (gradients of about five per cent will adequately shed water). The Vic-BPEM provides the following guidance for designing the pre-settlement cap and final surface profile:	The pre-settlement landfill cap has been designed at a slope of 1 vertical in 5 which is seen as the optimum configuration to achieve reasonable landfill airs term stable slope that can easily be rehabilitated and is also able to accommon settlement whilst maintaining the ability to shed excess surface water off the car	
		Where the proposed after use of the landfill require a gradient of less than 5% the cap design may need to incorporate additional levels of protection	The finished and capped landfill surface will be progressively rehabilitated to be post closure land use. If planting of native species is required the plants will be approved locally endemic species mix. Plants will be selected with root struct pose a threat of penetrating the LLDPE geomembrane and GCL capping laye	
		 Caps should not be steeper than 20% Since compaction of wastes along near-vertical side walls is difficult, the wastes along the walls of the landfill may exhibit the highest initial rate of settlement. The landfill cap needs to make allowance for this by providing sufficient thickness of the cap to ensure that run-off from the cap is not collected in depressions along the perimeter of the landfilled area 		
		The landfill aftercare program must include inspections of the cap, checking for differential settlement and indicators that the integrity of the low-permeability cap has been compromised, and		
		The use of plants on the landfill caps must consider the particular requirements of the cap design, and vegetation used must be compatible with the cap design.		
8.1.6	Landfill Cap	The Vic-BPEM requires that the design seepage rate of the cap does not exceed 75 per cent of the design seepage rate of the landfill liner.	Golder Associates has undertaken the leakage rate assessment of the landfill systems and confirmed the appropriate leakage rates have been achieved. T liner is deemed best-practise.	
		It also stipulates topsoil, vegetation and drainage considerations to minimise erosion and seepage.		
8.1.7	Alternative Landfill Cap	The Vic-BPEM stipulates the considerations in relation to the soil properties and other criteria, including compaction, when designing phytocaps.		
8.1.8	Low-Risk Rural Landfills – Indicative Phytocap Design	The Vic-BPEM stipulates the considerations in relation to the soil properties and other criteria, including compaction, when designing phytocaps for low-risk rural landfills.	The proposed Allawuna landfill is not deemed a low-risk rural landfill.	
8.2	Aftercare Management	The Vic-BPEM states that until the waste within the landfill has sufficiently decomposed or stabilised such that it no longer presents a risk to the environment, the landfill must be managed to prevent any environmental impact.	Once the proponent is of the opinion that the landfill has stabilised to such a c no longer the need to undertake further site maintenance and monitoring, a re an appropriately experienced consultant will be presented to the DER setting for the request to cease maintenance and monitoring activities. The DER will determination as to whether the maintenance and monitoring can be ceased.	
		 The following aftercare management requirements must be considered: Maintenance of landfill cap, in particular to: Prevent/control erosion 	There are no Environmental Auditors in WA specifically in relation to landfills Contaminated Sites Legislation). If regular groundwater monitoring indicates contaminated groundwater plume below the landfill, the site will be registered	

1	Conclusions
r change in e site after use.	Not applicable.
5 horizontal (20%), rspace and a long- nodate waste capped surface. b become suitable for be selected from an ctures that do not vers.	Complies.
ill lining and capping The proposed basal	Complies.
	Not applicable.
	Not applicable.
degree that there is report prepared by g out the justification ill then make a l.	Complies.
s (in WA there is the s that there is a d as a	



Siting, Design, Operation and Rehabilitation of Landfills (EPA Victoria, October 2014) Specification			Allawuna Farm Landfill Works Approval Application
	Section	Summary	Proposal
		 Restore depressions and seal and monitor cracks in the cap caused by settlement, and Restore/maintain vegetation. 	Contaminated Site.
		 Restore/maintain vegetation. Maintenance and operation of leachate collection and treatment system 	
		 Maintenance and operation of landfill gas-extraction system 	
		Environmental monitoring of:	
		Groundwater	
		Surface water	
		Landfill gas	
		Leachate, and	
		Settlement.	
		 Funds should be allocated during the operational life of the landfill to provide for aftercare management 	
		 Environmental auditing to examine, among other things, the results of monitoring of groundwater, surface water, landfill gas and leachate. 	
8.2.1	Buffers and Measurements	To manage landfill gas impacts the Vic-BPEM stipulates the post-closure buffer required for different types of landfill.	There is a 1.9 km buffer to the nearest neighbouring structure. The landfill but place at least until the site is no longer required to undertake any maintenance
		Type 2 Landfill = 500 metres from building or structures	(as determined by the DER).
		Type 3 Landfill = 200 metres from buildings and structures.	
8.2.2	Buffer Distances and Encroachment	The Vic-BPEM requires consideration of any proposed developments or any other works within the landfill buffer that might pose a safety risk by potentially providing preferential pathways for subsurface landfill gas migration, or providing an environment where landfill gases can accumulate to dangerous levels.	Due to the rural setting, it is not anticipate that there will be any buffer encroad landfill.
В	Appendix Technical Guideline	Appendix B of the Vic-BPEM details the technical requirements for landfill design.	A Construction Specification has been prepared in accordance with the techni Appendix B of the Vic-BPEM and is included in the Allawuna Landfill WAA as
D	Appendix Geomembranes	Appendix D of the Vic-BPEM details the technical requirements for geomembranes. The quality of the geomembranes shall be in accordance with the requirements of the Geosynthetic Research Institute	Details of liner specifications, installation and quality control are included in the Specification in the Allawuna Landfill WAA Appendix M.
		(GRI) – <i>GM13</i> and <i>GM17</i> .	A 2 mm thick HDPE geomembrane liner will have properties as nominated in the Specification in accordance with the Vic-BPEM requirements. The contractor prepare and submit a liner construction plan to the Superintendent and QAI of party quality surveillance is proposed during the construction of the composite
E	Appendix Geosynthetic Clay Liners	Appendix E of the Vic-BPEM details the technical requirements for Geosynthetic Clay Liners. The quality of the geosynthetic clay liner (GCL) shall be in accordance with the requirements of the Geosynthetic	Details of liner specifications, installation and quality control are included in the Specification in the Allawuna Landfill WAA Appendix M.
		Research Institute GRI-GCL3.	The GCL will have properties as nominated in the Technical Specification in a Vic-BPEM requirements.
F	Appendix Geotextiles	Appendix F of the Vic-BPEM details the technical requirements for Geotextiles. The quality of the geotextile shall be in accordance with the requirements of the Geosynthetic Research Institute (GRI) — $GT12(b)$ or $GT12(a)$.	The cushion geotextile layer will have properties as nominated in the Technica accordance with the Vic-BPEM requirements.

https://aupws.golder.com/sites/147645033alluwunafarmpeerreview/correspondence out/147645033-013 risk assessment and waa/appendix v - vic bepm compliance table.docx

1	Conclusions
ouffers will remain in ce and monitoring	Complies.
achment around the	Not applicable.
nical requirements of s Appendix M.	Complies.
the Technical of the Technical or will be required to of the project. Third te liner system.	Complies.
the Technical accordance with the	Complies.
cal Specification in	Complies.

