

Project: Leonora Waste Pond Duplication

Tenderer:

Date:



ITEM	DESCRIPTION	UNIT	QTY	RATE	TOTAL
------	-------------	------	-----	------	-------

PRELIMINARIES

- Mobilisation / Demobilisation
- Contractors Site Facilities and Services
- Insurances
- Site Fencing
- Site Access
- Construction Industry Training Fund Levy (0.2% of Contract Sum)
- Scheduled Testing
- As Constructed Details
- Survey / Supervision/Project Management
- Occupational Health and Safety Management
- Safety Management Plan
- Dust, Noise and Vibration Management Plan
- Locate and Protect Existing Services
- Final Cleanup
- Other Items Necessary for Completion of the Works
- Contingency**

Item	1		
Weeks	10		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Item	1		
Prov Item	1	\$	\$

SUBTOTAL PRELIMINARIES

\$

SITWORKS

Clearing and Grubbing

Strip and Stockpile Topsoil

Remove Topsoil off Site

Cut to Spoil

Cut to Fill

Proof Rolling (Foundation Prep)

Import and Compact Fill

Geotechnical Certification of Earthworks

Construction Water

Supply and Install Geosynthetic Clay Liner

Supply and Install 1.5mm Smooth/Textured HDPE Geomembrane

Dust supression

Item	1		
Prov m²	4500		
Prov m³	450		
m ³	2000		
m ³	2900		
m ²	4500		
Prov m³	500		
Item	1		
Item	1		
m ²	3500		
m ²	3500		
Item	1		

SUBTOTAL SITEWORKS

\$ -

DRAINAGE

DN100 Slotted PVC Subsoil

Open Pump Dewatering and Metal Bedding

1050 Monitoring Well

m	150		
Prov m	150		
No.	1		

SUB TOTAL STORMWATER DRAINAGE

\$ -

Project: Leonora Waste Pond Duplication



SUMMARY

PRELIMINARIES

SITWORKS

STORMWATER DRAINAGE

SUBTOTAL (EXCL GST)

ADD GST ALLOWANCE 10%

TOTAL CONSTRUCTION CONTRACT (INCL GST)

\$	-
\$	-

Please note it should not be assumed that the Priced Bill of Quantities lists all items required.