Main Roads WA - Revegetation Plan for Pastoral Areas

Condition 13(a), CPS 818/6

Date: 17 July 2012 **Project:** GNH Realignment Camp Site

Manager: Main Roads WA.

Location and size of clearing:

For project areas located within the pastoral / rangelands region north of the agricultural area as described in the Environmental Protection Authority's Position Statement No.2. The project will require clearing of approximately 4.5ha of native vegetation within the Town of Port Hedland, approximately 20kms south of Port Hedland and 5kms south of South Hedland.

Location and size of revegetation:

Primarily for areas that were cleared for the construction of a temporary camp in relation to the Great Northern Highway Realignment project. (See attached map for project location).

Clearing description:

Machine clearing.

Revegetation description:

Replacement of topsoil material regeneration.

Reason for revegetation:

Revegetation of temporary cleared areas, in accordance with condition 13(a) of clearing permit CPS 818/6.

Revegetation / rehabilitation requirements:

Site preparation:

All vegetation will be cleared from the works area and non-weed infested vegetation is stockpiled. Stockpiled vegetation will be placed in a manner that will prevent damage to adjacent vegetation by machinery. Weed infested vegetation will be disposed of at an appropriate site and not used for revegetation purposes. Burning of the cleared vegetation will not be permitted.

Topsoil will be stripped to a maximum depth of 100mm, and will be stored in a weed free (as far as possible) area, as close as possible to the area to be rehabilitated. Topsoil will be placed in windrows of less than 1.5m in height and reinstated as soon as practicable to maintain viability of in-situ seeds.

Weed control:

Appropriate weed control will be carried out when weeds are present, both prior to topsoil stripping and where weeds become established on or between the stockpiled materials. Weed control will take place prior to the respreading of topsoil to ensure weeds are killed and not transported to other areas.

Control measures include the removal of weeds to an approved dumpsite, or treatment of weeds such as by using herbicides mixed in accordance with manufacturer's instructions and applied by a licensed operator. Where practicable, weeds will be removed prior to or when they are in flower, and prior to seeding.

All machinery will be cleared of soil build up and vegetative material before entering and leaving the site to help minimise the transportation of weeds and their seeds.

Exposed areas such as bare batters and borrow pits shall be promptly rehabilitated to reduce the potential for weed establishment. Where works are adjacent to good quality vegetation, where weeds from within the project area are likely to spread to and result in environmental harm to the adjacent area, those weeds will be controlled annually until 12 Dec 2010..

Main Roads WA - Revegetation Plan for Pastoral Areas

Condition 13(a), CPS 818/6

Regeneration / direct seeding / planting at an optimal time:

The following rehabilitation works are undertaken on areas of disturbed earth requiring rehabilitation:

- Topsoil is uniformly respread to a typical depth of 100mm over the project area. In project areas where topsoil has not been removed and/or is not available, other substrate, such as gravel, may be substituted as a growth medium.
- Project areas will be ripped to a minimum depth of 200mm deep with rip lines approximately 300mm apart. Where slopes are present, rip lines shall follow natural contours.

The following rehabilitation works are undertaken at borrow / gravel pits:

- Overburden and then topsoil will be uniformly and evenly spread over the disturbed areas
 of the pit. Depending on the slope of drainage lines within the pit, small swales from the
 topsoil will be formed to reduce erosion velocities and encourage the deposition of seeds.
- The whole of the existing pit floor, including drainage lines, will be ripped to a depth of 300-500mm deep with rip lines between 500-800mm apart (if the material in the pit is able to be ripped).
- All stockpiled vegetation will be spread along the contour and the pit floor to help promote seed deposition and to reduce erosion velocities.

Vegetation establishment period:

The vegetation establishment period is for at least twelve months following the completion of the works. During this period, maintenance and monitoring will be undertaken (see below).

Ongoing maintenance and monitoring:

After revegetation works, revegetated areas will be inspected every six months for a year then annually for a minimum of two years to monitor and control weeds and to measure the effectiveness of revegetation works.

When unwanted weed foliage cover exceeds 25% after the initial two year period, further actions will be implemented to monitor and control these weeds. The additional monitoring and weed control will be conducted annually until 12 Dec 2010 or until the unwanted weed foliage cover falls below 25%, whichever is sooner.

Monitoring commitments:

Post revegetation site inspections will be carried out annually for a minimum of two years to monitor unwanted weeds and measure the effectiveness of revegetation works. Monitoring of sites where unwanted weed foliage cover exceeds 25% after the initial two year period will continue annually until 12 Dec 2010 or until the unwanted weed foliage cover falls below 25%, whichever is sooner.

Management commitments:

Undertake annual weed control of unwanted weeds annually until 12 Dec 2010 or until the unwanted weed foliage cover falls below 25%, whichever is sooner.

Agencies consulted and submissions received:

Nil.




Figure 1: Project area cleared and requiring revegetation (shaded in orange)